



1	Manufacturer: Kaishan Compressor USA		
2	Model Number: KRSP2-150-100 VSD		Date: 07/12/21
	<input checked="checked" type="checkbox"/> Air-cooled <input type="checkbox"/> Water-cooled		Type: Screw
			# of Stages: 2
3*	Full Load Operating Pressure ^b	100	psig ^b
4	Drive Motor Nominal Rating	150	hp
5	Drive Motor Nominal Efficiency	95.4	percent
6	Fan Motor Nominal Rating (if applicable)	5 & 1.5	hp
7	Fan Motor Nominal Efficiency	89.5 & 87.5	percent
8*	Input Power (kW)	Capacity (acfm) ^{a,d}	Specific Power (kW/100 acfm) ^d
	136.3	824	16.54
	96.8	577	16.78
	84.5	494	17.11
	72.2	412	17.52
	58.6	330	17.76
9*	Total Package Input Power at Zero Flow ^{c, d}	0.0	kW
10	Isentropic Efficiency	78.40	%
11	<p>Note: Graph is only a visual representation of the data in Section 8 Note: Y-Axis Scale, 10 to 35, + 5kW/100acfm increments if necessary above 35 X-Axis Scale, 0 to 25% over maximum capacity</p>		

*For models that are tested in the CAGI Performance Verification Program, these items are verified by the third party administrator. Consult CAGI website for a list of participants in the third party verification program: www.cagi.org

NOTES:

- a. Measured at the discharge terminal point of the compressor package in accordance with ISO 1217, Annex E; ACFM is actual cubic feet per minute at inlet conditions.
- b. The operating pressure at which the Capacity (Item 8) and Electrical Consumption (Item 8) were measured for this data sheet.
- c. No Load Power. In accordance with ISO 1217, Annex E, if measurement of no load power equals less than 1%, manufacturer may state “not significant” or “0” on the test report.
- d. Tolerance is specified in ISO 1217, Annex E, as shown in table below:
NOTE: The terms "power" and "energy" are synonymous for purposes of this document.



Volume Flow Rate at specified conditions		Volume Flow Rate	Specific Energy Consumption	No Load / Zero Flow Power
m^3 / min	ft^3 / min	%	%	%
Below 0.5	Below 17.6	+/- 7	+/- 8	+/- 10%
0.5 to 1.5	17.6 to 53	+/- 6	+/- 7	
1.5 to 15	53 to 529.7	+/- 5	+/- 6	
Above 15	Above 529.7	+/- 4	+/- 5	